



NOTES

1. BARE COPPER GROUNDING CONDUCTOR SHALL BE LOOPED AROUND ANCHOR BOLTS ONE TIME AND CONNECTED TO EACH ANCHOR BOLT BEFORE CONTINUING DOWN TO THE GROUNDING PLATE.
2. IN AREAS WHERE R/W PERMITS, THE CONCRETE BASE SHALL BE PLACED AT THE BACK EDGE OF THE SIDEWALK.
3. REFER TO STD. DWG. 331 FOR SERVICE PEDESTAL SETBACK AND ORIENTATION.

PROFESSIONAL ELECTRICAL ENGINEER STAMP ON FILE		AGENCY APPROVED	B	C	H	L	M	N	R
SPECIFICATION REFERENCE		UNIFORM STANDARD DRAWINGS CLARK COUNTY AREA							
501	PORTLAND CEMENT CONCRETE	SERVICE PEDESTAL FOUNDATION TRAFFIC SIGNAL							
623	TRAFFIC SIGNALS & STREETLIGHTING								
DATE 08-08-19		DWG. NO. 726							